

STANDING CONFERENCE OF PUBLIC ENTERPRISES
(An Apex body of Public Enterprises)
SCOPE Minar, Laxmi Nagar, Delhi-110092
Ph: 22458178, Fax: 011-22501185
e-mail: scope_tech2006@yahoo.com

CORRIGENDUM-1

Refer to our NIT NO. **SCOPEMINAR/MMO/23-24/ 182** dated 05.01.2024, for "Supply & installation of Cassette type Air conditioner system in Recreation room at 3rd floor for **SCOPE Minar, Laxmi Nagar, Delhi-110092.**", the date of Submission & opening of tender has been extended as per following:

- | | | |
|---|---------------------------------------------|-----------------------------|
| a | Last date of E-Bid submission | : 30.01.2024 Up to 03:00PM. |
| b | Last date of submission of hard copy of EMD | : 30.01.2024 Up to 03:00PM |
| c | Tender opening date & time (Technical) | : 30.01.2024 at 03.30PM |
| d | Tender Opening date & time (Financial) | : To be intimated later |

For details please visit our website www.scopeonline.in and <http://scope.ewizard.in>


Sr. Manager (Tech.)

SCOPE OF WORK

The scope of work includes the following:-

1. Demolishing of existing MS structure including stacking the same at site within 50 mtr lead as per directions of EIC.
2. Demolishing of existing brick work / cement concrete / temporary flooring, stone flooring, wall cladding etc. including stacking of serviceable material and disposal of unserviceable material within 50 Mtrs lead.
3. Shifting of mulba / dabries from terrace passage to outer parking of SCOPE Complex manually including all taxes etc. complete in all respect as per directions of Engineer-In-Charge.
4. Disposal of of unserviceable materials by mechanical means (By Trucks / Tempo) from SCOPE Complex to outside the municipal limits as per direction of Engineer-in-charge.
5. Preparation of surface by removing loose particles / scrapping of walls to remove loose plaster etc. shall be in the scope of the contractor. Nothing shall be apid extra on this account.
6. Execution of the items mentioned in BOQ, complete in all respect as per directions of Engineer In-Charge.
7. Supply & laying / fixing / installing of all the materials required to carryout above said works, job including all consumables are also in the scope of work of contractor. Nothing shall be paid extra on this account.
8. Providing and laying 25mm thick Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) as per DSR 2021 item no. 11.26.1.
9. Scope of work also includes the cost of making cutouts for electrical fittings or other fittings as required at site.
10. Proper level & design of false ceiling / partitions etc. as per requirement is to be achieved by the contractor.
11. Supply & laying / fixing / installing of all the materials required to carryout above said works, job including all consumables are also in the scope of work of contractor. Nothing shall be paid extra on this account.
12. Contractor shall got approved the sample of materials before supply at site.
13. As works are to be carried out in locations where offices of the constituents of SCOPE Complex are functioning, contractor has to work in such manner that constituents face minimum disturbance. For this purpose contractor may have to work in late hours or after office hours or on holidays including Sundays etc. after taking permission from SCOPE.
14. The work shall be carried out in such a way that no damage to the property of SCOPE / Building occurred and in case of any damage to the same contractor is liable to replace / provide the same.

